D-424 Josiah Bayly House Cambridge Mid 19<sup>th</sup> century Private

The Orem house, historically known as the Josiah Bayly house, is a prominent structure on High Street with its location across from the courthouse square and next to the cemetery of Christ Episcopal Church. While the popular history of the house points to a late 18<sup>th</sup> or early 19<sup>th</sup> century construction date, the exterior evidence suggests that an older structure may have been reworked extensively during the third quarter of the 19<sup>th</sup> century, thereby yielding its present appearance. The two-and-a-half story, five-bay, double-pile frame dwelling has a Victorian cross gable on its southeast elevation and mid nineteenth century sash windows light the entire structure.

Josiah Bayly practiced law in Cambridge and he purchased this lot from the Vestry of Great Choptank Parish in September 1796. He and his family occupied the house on this lot, and as well financed the construction of the small law office directly on the boundary with the church land. (See 189) Josiah worked in this law office as a local attorney, and later served at higher levels as the Attorney General for the State of Maryland. After his death in the mid 1850s, the property passed down through his family to his son, Dr. Alexander Hamilton Bayly (1814-1892), who is recorded as occupying the house next door (See D-10), while his son, Edgar Bayly and family resided on this lot. In 1892, following the death of Alexander H. Bayly, M.D., the houses and sizable town acreage bordering High, Church, William and Mill streets, were sold by J. Washington and Fannie C. Bayly of Louisville, Kentucky, to Isabel B. Shepherd for \$7,500. Seven years later, the property was transferred to George W. Dawson, Sr. (d. 1913), in whose

estate the property remained at his death. His heirs sold the High Street house, office and lot to Earle W. Orem in February 1917, whose descendant maintains ownership to the present time.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

historic	Josiah	Bayly House				
other						
2. Location						
street and number	er 209 Hig	h Street				not for publication
city, town	Cambrio	ige				vicinity
county	Dorches	ster				
3. Owner o	f Property	(give names and mailin	g addresses of all	l owners)		1-7
name	Reginal	d C. Orem				
street and number	er 209 Hig	h Street			telephone	
city, town	Cambrio	dge	state MD		zip code	21613
city, town	Cambridge	Dorchester County Cle tax map 30	1 tax parcel	liber 16	PLC 270 tax ID	folio 634 number 7-170211
5. Primary Con Con Dete	Cambridge  Cambridge  Location of  tributing Resource in  tributing Resource in  ermined Eligible for the  ermined Ineligible for  orded by HABS/HAE  oric Structure Report	Additional Data  National Register District Local Historic District he National Register/Maryl the National Register/Maryl	and Register			
5. Primary Con Con Dete	Cambridge  Cambridge  Location of  tributing Resource intributing Resource intermined Eligible for the termined Ineligible for orded by HABS/HAE oric Structure Reporter:	Additional Data  National Register District Local Historic District The National Register/Maryla The National Register/Maryla The National Register/Maryla	and Register			

7	Des	ori	nti	on
1.	Des	CH	μu	OH

#### Condition

	_ excellent	deteriorated
х	_ good	ruins
	_ fair	altered

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

### DESCRIPTION SUMMARY

The Josiah Bayly house stands at 209 High Street in the center of Cambridge, Dorchester County, Maryland. The two-and-a-half story center hall/double pile plan frame house, estimated to date to the early nineteenth century with third quarter of the nineteenth century modifications, is supported by a raised common bond brick foundation, and the exterior is clad with beaded vinyl siding. The steeply pitched cross gable roof is finished with fiberglass shingles. Stretching across the front of the house is an early twentieth century hip roofed porch. Attached to the back of the house is a single-story shed roofed addition.

### GENERAL DESCRIPTION

The Josiah Bayly house is located at 209 High Street across the street from the Dorchester County Courthouse. The two-and-a-half story, five-bay by three-bay frame dwelling is supported on raised brick foundation and the exterior is clad with beaded vinyl siding. The steeply pitched gable roof is covered with fiberglass shingles. Piercing each gable end of the center hall plan house is a large interior end brick chimney stack. While historical research has estimated this house to date to the late 18<sup>th</sup> or early 19<sup>th</sup> century, exterior finish features indicate that the house experienced a significant reworking during the third quarter of the nineteenth century with the introduction of a new sidelighted entrance and new six-over-six sash windows on all sides.

The southeast (main) elevation is a symmetrical five-bay façade with a center entrance and flanked sidelights and transom fitted with leaded glass panes. To each side of the entrance are pairs of six-over-six sash windows surviving with late 19<sup>th</sup> century shutter hardware. The entire first floor is sheltered by a hip roofed porch supported on square posts enhanced with simple curved corner brackets. Stretching between posts is rectangular baluster railing with a molded handrail. The second floor is lighted by an evenly spaced series of six-over-six sash windows, and the centered cross gable is likewise pierced by a six-over-six sash window. The edge of the roof is finished with an enclosed boxed cornice.

The gable ends are defined by asymmetrical fenestrations of six-over-six sash windows on either side of the interior end chimney stack. Rectangular cellar window openings pierce the foundation. In the gable end, a single six-over-six sash window is centered between diverging flues of the chimney stack. A cellar window opening on the northwest side retains horizontal metal bars.

The interior was not seen on the initial field visit.

Period	Areas of Significance	Check and j	ustify below		
1600-1699 1700-1799 x 1800-1899 1900-1999 2000-	agriculture archeology x architecture art commerce communications community planning conservation	economics education engineering entertainment/ recreation ethnic heritage exploration/ settlement	health/medicine industry invention landscape architecture law literature maritime history military	performing arts philosophy politics/government religion science social history transportation other:	201
Specific dates			Architect/Builder		
Construction d	ates				
Evaluation for:			8		
	National Register	N	Maryland Register	xnot evaluated	

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance projects, complete evaluation on a DOE Form – see manual.)

### SIGNIFICANCE SUMMARY

The Orem house, historically known as the Josiah Bayly house, is a prominent structure on High Street with its location directly across from the courthouse square. While the popular history of the house points to an late 18th or early 19th century construction date, exterior evidence indicates an older structure was reworked extensively during the third or fourth quarter of the nineteenth century. Josiah Bayly was an attorney in Cambridge and he purchased this lot from the Vestry of Great Choptank Parish in September 1796. The occupied a house on the lot and financed as well the construction of the small law office directly on the boundary with the church land. (See D-189) Josiah Bayly practiced law in Cambridge during the second quarter of the 19th century as well as serving as an Attorney General for the State of Maryland. After his death in mid 1850s, the the property passed down through family to his son Dr. Alexander Hamilton Bayly (1814-1892), who is recorded as occupying the house next door when the Lake, Griffing and Stevenson atlas was published in 1877, while his son, Edgar Bayly and him family occupied the house on this lot, In 1892, following the death of Alexander H. Bayly, M.D., the houses and large town acreage bordering High, Church, William and Mill street were sold by J. Washington and Fannie C. Bayly of Louisville, Kentucky to Isabel B. Shepherd for \$7,500.2 Seven years later, the property was transferred to George W. Dawson, Sr. (d. 1913), in whose estate the property remained at his death. His heirs sold the High Street house and lot to Earle W. Orem in February 1917, 3 whose descendants maintain ownership to the present time.

<sup>&</sup>lt;sup>1</sup> John L. Graham, *The 1877 Atlases and Other Early Maps of the Eastern Shore of Maryland*. Wicomico Bicentennial Committee, p. 77.

Dorchester County Land Record, CL 16/558-59, 1 June 1892, Dorchester County Courthouse.
 Dorchester County Land Record, WHM 3/87, 3 February 1917, Dorchester County Courthouse.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-424

Name

Josiah Bayly House

**Continuation Sheet** 

Number 8 Page 1

Josiah Bayly House 209-11 High Street Cambridge, Dorchester County, Maryland Map 301, Parcel 16

CHAIN-OF-TITLE

PLC 270/634

Reginald C. Orem

to

11.12.1991

Leah Orem Gore and Oliver R. C Gore, Jr.

PLC 247/91

Reginald C. Orem and Hazel R. Orem

to

10.20.1987

Reginald C. Orem

PLC 117/283

Earle W. Orem

to

12.21.1959

Reginald C. Orem and Hazel R. Orem

No. 33 and 35 High Street

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Name

Josiah Bayly House

**Continuation Sheet** 

Number 8 Page 2

RSM 75/483

V. Calvin Trice, Trustee

to

6.30.1951

Earle W. Orem

JFD 25/394

Earle W. Orem

to

2.17.1928

Birdsel D. Orem

(same land conveyed to said Earle Orem by J. Simmons Dawson,

et al., 2.3.1917, WHM 3/87)

WHM 3/87

J. Simmons Dawson, George Dawson, Frank W. Dawson, Sarah D.

Preistman

to

2.3.1917

Earle W. Orem

Whereas George W. Dawson, Sr. died intestate, on or about 8.22.1913

CL 23/377

Isabel B. Shepherd of Washington, D.C.

to

4.25.1899

George H. Dawson, Sr.

Lot No. 1

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-424

Name

Josiah Bayly House

**Continuation Sheet** 

Number 8 Page 3

CL 16/558-59

J. Washington E. Bayly and wife, Fannie C. Bayly, City of

Louisville, Kentucky

to

6.1.1892

Isabel B. Shepherd

\$7,500 land which Alexander H. Bayly, M.D. died seized, bordering

High, Church, William and Mill streets

1877 Atlas

Cambridge Town Map-Residence of Edgar Bayly

HD 9/503

Vestry of Great Choptank Parish

To

9.6.1796

Josiah Bayly

Lot No. 2 on the main street of Cambridge-in accordance with

an Act of Assembly of 1791 to sell

## 9. Major Bibliographical References

Inventory No. D-424

Dorchester County Land Records, various volumes, Dorchester County Courthouse.

John L. Graham, The 1877 Atlases and Other Early Maps of the Eastern Shore of Maryland, Wicomico Bicentennial Committee, 1976.

## 10. Geographical Data

Acreage of surveyed property Acreage of historical setting Quadrangle name

17,871 square feet 17,871 square feet +/-

Cambridge, MD Quadrangle

Quadrangle scale: 1:24,000

#### Verbal boundary description and justification

The metes and bounds of this property are coincidental with the current boundary of the lot.

## 11. Form Prepared by

name/title	Paul B. Touart, Architectural Historian		
organization	Chesapeake Country Heritage & Preservation	date	2/24/2010
street & number	P. O. Box 5	telephone	410-651-1094
city or town	Westover	state	Maryland 21871

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust DHCD/DHCP 100 Community Place Crownsville, MD 21032-2023 410-514-7600

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Name Josiah Bayly House Continuation Sheet


Number 9 Page 1



# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Name Josiah Bayly House Continuation Sheet


Number 9 Page 2




# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Name Josiah Bayly House Continuation Sheet

Number 9 Page 3



D-424, Josiah Bayly House, southeast elevation, Cambridge, Dorchester County, Maryland, 2.2010, Paul Baker Touart, photographer, Negative/MD Historical Trust



D-424, Josiah Bayly House Cambridge, MD Quadrangle



D-424 JOSIAH BAYLY (TONSE CAMBRIDGE BORITESTER C. NO. SOUTHERST ELEVATION 2. 2010, PAUL B. TOUART, PITUTU. NEGATIVE / MD. HISTORICAL TAUST

1 of 1

### MARYLAND HISTORICAL TRUST WORKSHEET

### NOMINATION FORM for the NATIONAL REGISTER OF HISTORIC PLACES, NATIONAL PARKS SERVICE

AND/OR HISTORIC:					
LOCATION					
STREET AND NUMBER:		. The Part of the			
209 High S	Street	7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7			
Cambridge					
STATE CAMEDI TOGE	4-3-6-1	c	DUNTY:	6 13304 -	
Maryland	Lands at	ite range being	Dorch	ester	
 CLASSIFICATION	,				
CATEGORY (Check One)		OWNERSHIP		STATUS	TO THE PUBLIC
☐ District	Public Private Both	Public Acquisition In Proces Being Co		○ Occupied ○ Unoccupied ○ Preservation work in progress	Yes: Restricted Unrestricted No
PRESENT USE (Check One or I	More as Appropris	ate)			
Commercial Ir	overnment ndustrial ilitary useum	☐ Park  ☑ Private Residence ☐ Religious ☐ Scientific		Transportation Other (Specity)	Comments
 OWNER OF PROPERTY	377311				
Reginald ( STREET AND NUMBER: 209 High ( CITY OR TOWN:			STATE:		
Cambridge			M	aryland	21613
LOCATION OF LEGAL DESC					20
COURTHOUSE, REGISTRY OF					
STREET AND NUMBER:		Courthouse			
CITY OR TOWN:	Street		STATE		
Cambridge				yland	21613
Title Reference	of Curren	nt Deed (Boo			
REPRESENTATION IN EXIST					ie
TITLE OF SURVEY:					
DATE OF SURVEY:		☐ Federal	☐ State	County	] Local
DEPOSITORY FOR SURVEY RE	ECORDS:				

S
m
Ш
_
z
S
-
20
_
0
_
0
Z
S

7.	DESCRIPTION	SEAR WELL							
					(Ch	eck One)			and the same of th
	COLLECTION	☐ Excellent	Good	☐ Fair	□ De	steriorated	Ruins	☐ ·Unexposed	
	CONDITION		(Check On	e)			(CI	heck One)	
		Altered	d	Uncliered			☐ Moved	> ○ Original Site	

Although this house was built sometime around 1796, it was added onto around the turn of the 19th century and now appears to be a much later house than it actually is. The interior, however, still retains much of the early woodwork.

This frame house is two and one half stories high and has a gable roof with a center gable. There is a pointed arch window in the gable. A one story porch extends across the five bay front, supported by rectangular posts and uncarved arched brackets. The eight panel door is flanked by rectangular sidelights and a transom light above.

PERIOD (Check One or More as	Appropriate)		
☐ Pre-Columbian	☐ 16th Century	18th Century	20th Century
☐ 15th Century	☐ 17th Century	19th Century	
SPECIFIC DATE(S) (If Applical	le and Known) 1796	, late 19th c.	
AREAS OF SIGNIFICANCE (Ch	eck One or More as Appropria	te)	
Abor iginal	☐ Education	☐ Political	Urban Planning
☐ Prehistoric	☐ Engineering	Religion/Phi-	Other (Specify)
☐ Historic	☐ Industry	losophy	
☐ Agriculture	- Invention	Science	
Architecture	☐ Landscape	☐ Sculpture	
☐ Arr	Architecture	☐ Social/Human-	
Commerce	Literature	itarian	
☐ Communications	Military	☐ Theater	
☐ Conservation	Music	☐ Transportation	

### History:

In September 1796, the trustees of Christ Church conveyed this property to Josiah Bayly to help pay for the church building. Bayly, a distinguished lawyer and our Fifth Attorney General of Maryland, built the present house with the exception of the part to the left as one enters, which was added by Mrs. Isabel Shepherd. Bayly's law office was next door (211 High Street). He died in 1846, leaving the property to his widow Ann A. Bayly. Mrs. Bayly died in June 1857, and after her death the property was sold to Dr. Alexander H. Bayly. Dr. Bayly died in 1892, leaving the property to his son Josiah W. E. Bayly of Louisville, Kentucky. He died in 1892 also, and the property was sold to Mrs. Isabel Shepherd.

### Significance:

Although altered sometime around the turn of the century this is one of the older houses on High Street, which possesses many houses of architectural significance ranging from pre-Revolution to early 20th century construction.

		llivane			e reprinted in Banner, April	
APHICAL D.	ATA				A Control of the Cont	
			Contract of the Contract of th	0	DEFINING THE CENTER	GITUDE COORDINATES R POINT OF A PROPERTY AN TEN ACRES
LATIT	JDE	LONGIT	TUDE	K	LATITUDE	LONGITUDE
egrees Minute	s Seconds		tes Seconds		Degrees Minutes Seconds	Degrees Minutes Second
		0				
0	18 m	0				
MATE ACREA	GE OF NON		PERTY:	1 1	And the Control of th	
PREPARED	ву					
D TITLE:		ore				
		ore,				DATE
therine	L. Mo	ore,				DATE
D TITLE: therine ATION AND NUMBER	L. Mo			Is	TATE	DATE
therine ATION  AND NUMBER Dute 3,	L. Mo			s	TATE Maryland	DATE
therine ATION  AND NUMBER Dute 3, TOWN:	L. Mo	2 -	view:			
	LATITUDE AND NG A RECTAPORT OF THE PROPERTY OF	LATITUDE Degrees Minutes Seconds O O O O O O O O O O O O O O O O O O O	ATITUDE AND LONGITUDE COORDINANG A RECTANGLE LOCATING THE PROPERTY OF THE PROP	ATITUDE AND LONGITUDE COORDINATES NG A RECTANGLE LOCATING THE PROPERTY  LATITUDE LONGITUDE Degrees Minutes Seconds O O O O O O O O O O O O O O O O O O O	ATTITUDE AND LONGITUDE COORDINATES NG A RECTANGLE LOCATING THE PROPERTY  LATITUDE LONGITUDE Degrees Minutes Seconds 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	LATITUDE AND LONGITUDE COORDINATES  NG A RECTANGLE LOCATING THE PROPERTY  LATITUDE  LONGITUDE  LATITUDE  LONGITUDE  Degrees Minutes Seconds  O  O  O  O  O  O  O  O  O  O  O  O  O

209 High Street Josiah Bayly House Cambridge, Maryland

PLC 117/284

Despite its early twentieth century vernacular appearance, this house was built sometime after 1796 by Josiah Bayly, Cambridge lawyer and tenth Attorney General of Maryland (1831-1846). The lot was originally part of the lands of Great Choptank Parish as laid out in the survey of 1706. In 1750, the church leased a portion of its land, including this lot, to John Caile (see 207 High Street). In 1794, the parish recovered its lease from Caile's heirs and two years later sold the land as three lots to raise money for a new church. Josiah Bayly purchased the middle portion for 150 pounds and erected the present house. On his death in 1846 the property passed to his widow and then to his son, Dr. Alexander Hamilton Bayly, who resided next door at 207 High Street until 1892. The house has remained in the possession of Joshiah Bayly's descendants to this day, except for the years 1899-1917. Earle Orem, father of the present owner, bought the house in 1917, added to the rear and remodeled the exterior as it now stands. The present owners acquired the house in 1959.

This house is significant from its historical association with one of Cambridge's most prominent figures of the early nineteenth century. From an architectural point of view, however, the exterior of the house is not in keeping with other houses of the same age on High Street. Sources:


Dorchester County Courthouse, Cambridge, Maryland.

Land Records.

Will Records.

Interview with Reginald and Hazel Orem, 209 High Street, owners.


Research by: Terrance P. Walbert



D-424 Josiah Bayly House 209 High St. Cambridge Cambridge Quad. Dorchester Co.



D-424 Josiah Bayly House 209 High St. Cambridge Cambridge Quad. Dorchester Co.





209 HIGH ST. , CAMBRIDGE, MD. - EAST FACADE, - C.L. MOTRE, 1976

3.3